

TECHNICAL SPECIFICATION

Execution of construction and craft works on the current maintenance of the building of the Embassy of the Republic of Serbia in Brussels - Main building					
	Description of the position	quantity	unit of measures	price per unit	price (EUR)
	Building craft works on the roof of the building				
1	Dismantling and removing chimney				
1.1	Dismantling a piece of chimney that relies on the neighboring building. Closing the holes on the wall where the chimney was, the handling of the vertical wall with the facade material, the waterproofing at the place where the chimney was, the installation of galvanized protection.	1	piece		
2	Repair of the damaged roof				
2.1	Repair of roof damage which is covered with tape. All sites that have damage should be repaired by placing a new part and or by watering the divided elements of the existing tape. It is especially necessary to repair any damage that exists on the edges of the metal dome and at the points of connection of the roof surface and the vertical walls of the adjacent buildings.				
2.2	Repair of glass dome: All dome on which there is damage at the points of connection of glass and metal construction should be repaired by watering with adequate waterproofing materials. The other parts of the dome should be adequately protected.				
2.3	Repair of the gutter on the roof: Wooden gutter should be repaired or replaced damaged gutter parts and put in gutter protection with a material that provides waterproofing	20	m1		
3	Carpentry works				
3.1	Replacing Damaged Roof Window: Double-winged wooden windows should be replaced with PVC windows with the same dimensions.	2	piece		

Execution of construction and craft works on the current maintenance of the building of the Embassy of the Republic of Serbia in Brussels - Main building

	Description of the position	quantity	unit of measures	unit price	price (EUR)
	Construction craft works on the 1st floor of the building				
4	<u>Repair of damaged ceilings and walls in the lounge and hallway</u>				
4.1	Repair damaged surfaces arising from the rupture of the sewer pipe and which are visible on the ceiling and walls on the first floor in the lounge and hallway. Painting with all necessary pre-works for this type of work, should be twice with semi-dispersive colors that fit into the existing color.				
5.	<u>Additional works</u>				
5.1	Preparation and securing of construction sites, removal of unnecessary building materials and cleaning after completion of works.				
TOTAL PRICE FOR MATERIAL AND WORKS (EUR):					